

**BLOUBERG LOCAL MUNICIPALITY**  
**PROJECT NO. BM19/17/18**  
**CONSTRUCTION OF INVERAAN CRECHE**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>AB005</b>	<b><u>INSTALLATION OF JUNGLE GYM</u></b>				
<b>1</b>	<b>Play Ground</b>				
<b>(LIC)</b>	Platform preparation as specified on drg BM003/12/13/P01				
<b>1</b>	Earthworks	m <sup>3</sup>	60		
<b>1.1</b>	Cut to spoil 150mm deep and compact to 93% MODAASHTO Density	m <sup>3</sup>	35		
<b>1.2</b>	75mm Blinding	m <sup>3</sup>	18		
<b>1.3</b>	110 brickwork	m <sup>2</sup>	9		
<b>1.4</b>	250mm ramp around the playground platform	m <sup>3</sup>	2		
<b>1.5</b>	Fill the play ground with Imported white sand or similliar quality.	m <sup>3</sup>	3375		
<b>(LIC)</b>	Supply, install the complete Wooden Jungle Gym as per client requirements and all sundries and fittings :	Sum	1		
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>					<b>R0.00</b>