

**BLOUBERG LOCAL MUNICIPALITY**  
**PROJECT NO. BM07/17/18**  
**CONSTRUCTION OF MAMEHLABE CRECHE**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>AB003</b>	<b><u>INSTALLATION OF BOREHOLES, PUMP &amp; TANKS</u></b>				
<b>1</b>	<b><u>DRILLING BOREHOLE</u></b>				
1.1	Water siting and drilling of the borehole up to 120m deep	Prov Sum	1	120,000.00	R120,000.00
1.2	Fully equip the borehole, install steel casing and submersible pump (including electrical connections and panel). (Provide geohydrological report to the Client before equipping the borehole)	Prov Sum	1	40,000.00	R40,000.00
<b>2</b>	<b><u>PVC STORAGE TANK INSTALLATIONS</u></b>				
<b>2.1</b>	<b><u>WATER TANK AND ELEVATED STEEL STAND</u></b>				
	Supply, install the elevated tank and all sundries and fittings scheduled on drawing BM004/12/13/T05 and T06 :	Sum	1		
<b>2.2</b>	Supply and install a 10000 liters plastic tank	No	1		
<b>2.3</b>	Supply and install Pressure Pump with fittings	No	1		
<b>2.4</b>	Connection to the community water pipeline as approved by the Client	Sum			Rate Only
<b>TOTAL CARRIED FORWARD TO SUMMARY</b>					<b>R160,000.00</b>