

BLOUBERG LOCAL MUNICIPALITY
PROJECT NO. BM07/17/18
CONSTRUCTION OF MAMEHLABE CRECHE

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
AB005	<u>INSTALLATION OF JUNGLE GYM</u>				
1	Play Ground				
(LIC)	Platform preparation as specified on drg BM003/12/13/P01				
1	Earthworks	m ³	60		
1.1	Cut to spoil 150mm deep and compact to 93% MODAASHTO Density	m ³	35		
1.2	75mm Blinding	m ³	18		
1.3	110 brickwork	m ²	9		
1.4	250mm ramp around the playground platform	m ³	2		
1.5	Fill the play ground with Imported white sand or similliar quality.	m ³	3375		
(LIC)	Supply, install the complete Wooden Jungle Gym as per client requirements and all sundries and fittings :	Sum	1		
TOTAL CARRIED FORWARD TO SUMMARY					R0.00