

**BLOUBERG LOCAL MUNICIPALITY
PROJECT NO. BM08/17/18
CONSTRUCTION OF MOKHURUMELA CRECHE**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
AB003	<u>INSTALLATION OF BOREHOLES, PUMP & TANKS</u>				
1	<u>DRILLING BOREHOLE</u>				
1.1	Water siting and drilling of the borehole up to 120m deep	Prov Sum	1	120,000.00	R120,000.00
1.2	Fully equip the borehole, install steel casing and submersible pump (including electrical connections and panel). (Provide geohydrological report to the Client before equipping the borehole)	Prov Sum	1	40,000.00	R40,000.00
2	<u>PVC STORAGE TANK INSTALLATIONS</u>				
2.1	<u>WATER TANK AND ELEVATED STEEL STAND</u>				
	Supply, install the elevated tank and all sundries and fittings scheduled on drawing BM004/12/13/T05 and T06 :	Sum	1		
2.2	Supply and install a 10000 liters plastic tank	No	1		
2.3	Supply and install Pressure Pump with fittings	No	1		
2.4	Connection to the community water pipeline as approved by the Client	Sum			Rate Only
TOTAL CARRIED FORWARD TO SUMMARY					R160,000.00